

# CURRENT PUBLIC WORKS PROJECTS

Updated 10-15-15

1. Price Road improvements: sidewalk and pavement rehabilitation from Delmar to Clayton (80% Federal, 20% City for Design, ROW, and Construction) –Gershenson Construction was awarded the construction phase for the Price Road improvements after publicly bidding the project. Work began on the project on Monday October 5, 2015. The contractor has milled the asphalt surface off the sidewalk and will be able to utilize the pavement below as a subgrade for the new concrete sidewalks. Concrete curb will be installed along the entire western edge of pavement. The asphalt roadway pavement will be milled and overlaid in Spring 2016. The contract completion date is June 2016.

2. Citywide Beautification Framework Plan

- Bids for the stepping stone installation were obtained and the stepping-stones will be installed Fall 2015 by Furfaro Landscaping.
- Christner has made further modifications to the concept design and cost estimates for Clayton/Warson Open Space Design and Path Connections to reflect the elimination of the decorative metal panels and the addition of a low stone wall. The next steps will be Ladue City Council approval, MoDOT's written approval for the project, and to identify and obtain funding.

3. Lay Road Improvements (80% Federal Funding, 20% City of Ladue Funding)

The City of Ladue was successful in obtaining federal funds for the Lay Road Improvements project which will consist of the installation of sidewalk on the west side of the road, storm sewer improvements, and pavement rehabilitation. The funding for the design phase is available 10/1/15. The request for qualifications for engineering consulting services has been issued and twenty submittals were obtained on September 29, 2015. The City will interview the three most qualified firms on Monday October 26, 2015 and select a firm. The engineering contractor will be presented to City Council for approval at the November 16, 2015 meeting.

4. Stormwater Needs Assessment (Stormwater Fund)

HR Green is nearing completion of the storm water needs assessment and has walked all of the creek channels in Ladue. They have developed a project website: <http://www.hlplanning.com/portals/ladue> where residents can learn more about the project and create data points for problem locations. This information is linked from the Public Works Departmental page on the City's website: <http://www.cityofladue-mo.gov/>. HR Green has mapped existing complaint data on file with MSD and the City. They have developed a basic hydraulic model of the entire City which may illustrate problem locations that have not been included on complaints from residents. Three Public Meetings were held in May and June with over 100 residents attending these meetings. HR Green developed a tri-fold mailer that has been distributed to all households within Ladue that explain the program, provide meeting dates, and the link to the project website. HR Green is in the process of verifying complaint data in the field and compiling all input and existing information into a final report. The

needs assessment is expected to be completed by November 2015. The next phase of the project will be the Storm Water Master Plan which will be developed in 2016. An interim phase to develop funding criteria and eligibility will likely begin in December 2015 prior to the Master Plan. A storm water committee will be formed to aid in this interim phase.